



झारखण्ड केन्द्रीय विश्वविद्यालय, राँची
CENTRAL UNIVERSITY OF JHARKHAND, RANCHI
(संसदीय अधिनियम के तहत 2009 में स्थापित केन्द्रीय विश्वविद्यालय)
(A Central University established by an Act of Parliament in 2009)

NOTICE INVITING TENDER

NO.: CUJ/EE/Auditorium Renovation /2018-19 /12

The Central University of Jharkhand, Brame, Ranchi – 835205, invites sealed tender from approved and registered contractor of CPWD/PWD/Govt. Organisation who are conversant to execute the works as under:

Name of work	Renovation work of Auditorium and other Miscellenious work at the premises of Central University of Jharkhand
Date of issue of Tender Document	29.08.2018 to 18.09.2018 (10:00 am to 4:00 pm)
Last Date of Submission Tender document	18.09.2018 (up to 5:00 pm)
Date/Time of opening of Tender	19.09.2018 (at 2:30 pm)
Time allowed for Completion project	2 1/2 Month (75) days.
Cost of Tender document (non-refundable)	Bank draft for Rs. 1000.00 (Rupees One Thousand only) in favour of “Central University of Jharkhand” payable at Ranchi.
Earnest Money	Rs 60,000/- (Rupees Sixty Thousand only) enclosed in the form of Bank Draft only in favour of “Central University of Jharkhand” payable at Ranchi along with bid document.

Tender document can be had from the Assistant Engineer (C/E), Central University of Jharkhand, Brambe, Ranchi-835205, on written request for issuing of tender documents, on all working days on payment of requisite cost of tender in form of Bank Draft in favour of “Central University of Jharkhand” payable at Ranchi or can be downloaded from University website <http://www.cuj.ac.in>.

1. The tender documents has to be submitted in three separate envelops, All the envelops should be enclosed in one big envelop super-scribing as

“Tender Documets for Renovation work of Auditorium and other Miscellenious work at the premises of Central University of Jharkhand “

a). **First Envelop** should be super-scribed as TECHNICAL BID containing the technical specification and firms credential.

b). **Second Envelop** should be super scribed as PRICE BID containing the quoted rate.

c). **Third Envelop** should be super scribed as EMD containing the EMD amount.

2. In case the Tender Document is downloaded from the website the cost of the tender document must be enclosed separately in **Fourth Envelop** super scribing as “**TENDER COST**” (non-refundable) attached along with tender in the form of Demand Draft in favour of Central University of Jharkhand, payable at Ranchi.

3. Tender submission should be accompanied with an Earnest Money Rs 60,000/- (Rupese Sixty Thousand only) (refundable) in the form of Demand Draft in favour of Central University of Jharkhand, payable at Ranchi.

4. The Tender received without EMD and Cost of Tender Document (in case the Tender downloaded from website) shall be summarily rejected. Tenderer or their authorised representative may be present on the day of opening of tender.
5. For clarification, if any, the same may be sought from the office of the Undersigned at the above address.
6. The complete tender documents are to be signed with seal and to be placed in the technical bid envelope along with necessary required catalogues/documents. The bidder shall submit satisfactory documentary proof.
7. Central University of Jharkhand reserves the right to reject any or all prospective applicants without assigning any reason and to restrict the list of tendered contractors to any number deemed suitable by it, if too many applications are received satisfying the basic prequalification criteria.
8. The decision of the Competent Authority of the University will be final and binding to all. Central University of Jharkhand reserve the right to accept or reject any tender and to annul the tender process and reject all tenders at any time, without assigning any reason.
9. The University reserves the right to increase or decrease the scope of work or split the job.
10. If any information furnished by the tenderer is found to be incorrect at any stage, the tenderer shall be liable to be debarred from tendering/taking up of work in Central University of Jharkhand. The Central University of Jharkhand reserves the right to verify the particulars furnished by the tenderer, independently.
11. Even though applicant may satisfy the above requirement, University reserve the right to disqualify if it is found that the tenderer has:
 - a. Made misleading or false representation or deliberately suppressed the information in the form of statement and enclosure required in the prequalification document.
 - b. Suppressed/hided the Record of proof performance such as abandoning works, not properly completing the contract, or financial failures/weakness etc.

Followind Documentry proof required for Technical Document

- a. Name of the Agencies/ Firms (Full address with Tel. No. and e -mail address)
- b. Registration No. of the Agencies/Firms and Registered with (details)
- c. PAN No.
- d. Experience (Please attach job completion certificate).
- e. Financial Turn over (2015-16,2016-17, 2017-18)

Executive Engineer
Central University of Jharkhand

FORMAT FOR TENDER

1. Name of Firm/Dealer:
2. Total quoted amount in Rs. =
3. Total quoted amount in word

4. VAT/GST Registration No.

5. Address of the Organisation:

Mobile No.:

Email-ID:

6. Signature with full name and seal

Date:

Place

Name of the Firm with Seal & signature

BOQ

Sl.No.	DSR-16	Items description	Qty	Unit	Rate	Amount
1	13.82.2	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. Two coats	5266.9	SQM		
2	14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	1144.10	SQM		
3	14.64.1	Finishing walls with water proofing cement paint of required shade : Old work (one or more coats applied @ 2.20 kg/10 sqm) over priming coat of primer applied @ 0.80 litres/10 sqm complete including cost of Priming coat.	2603.1	SQM		
4	13.26	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.	174.89	SQM		
5	14.1.1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground all complete as per directions of Engineer-In-Charge. : With cement mortar 1:4 (1 cement : 4 fine sand)	174.89	SQM		
6	12.52.1	Providing and fixing tiled false ceiling of specified materials of size 595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanised butterfly level clips of size 85 x 30 x 0.8 mm	263.38	SQM		

		<p>spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge. GI Metal Ceiling Lay in plain Tegular edge Global white color tiles of size 595x595 mm, and 0.5 mm thick with 8 mm drop; made of G I sheet having galvanizing of 100 gms/sqm (both sides inclusive) and electro statically polyester powder coated of thickness 60 microns (minimum), including factory painted after bending.</p>			
7	12.45.2	<p>Providing and fixing false ceiling at all height including providing and 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound , jointing tapes , finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with : 12.5 mm thick tapered edge gypsum fire resistant board conforming to IS: 2095- Part I</p>	423.63	SQM	

8	15.57	Dismantling aluminium/ Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable surplus material and stacking of serviceable material with in 50 meters lead as directed by Engineer-in-charge.	535.44	SQM		
9	15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	108.69	SQM		
10	4.1.2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:1½:3 (1 Cement: 1½ coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size).	3.82	m3		
11	NDSR	Repair maintenance and servicing of Duct Acs of 30 ton including parts like compressor, contactor, repair/repalcement of duct completed in all respect etc.	1	No.		
12	NSDR	Providing and fixing of water proofing ISI Type- 3 Grade-I Bitumin Tar felt of thickness 2-4 mm of roll lenth 30 m over precoated galvanized iron profile sheets. Complete the job in all respect as per direction of Engineer in charge.	60	nos.		
					Sum Total (A)	
					GST@12% on (A)	
					Total (A)	
Electrical work						
Sl.No.	Item code	Items	Qty	Unit	Rate inclusive GST	Amount
1	M.R	Suplly of ceiling fan make Orient, Usha, Havel, Polar etc. Blade size- 1200 mm (48 Inches) Super reliable and efficient copper motor Number of Poles: 12 Power consumption: 78 Watts	150	nos.		
2	M.R	Aluminium Armoured cable 1.1 KV grade 35 Sq-mm x 4 core MAKE Havel, KEI, Anchor, Plycab etc.	80	m		
3	M.R	High speed Wall mounted fan 16" make Orient, Usha, Havel, Polaretc.	20	Pc		
4	M.R	Havel, Orient, Usha, Polar etc. Turbojet 450mm 1400 RPM hevey Duty Single phase Exaust fan	7	Pc		
					Sum Total (B)	
					Grand Total (A+B)	

1. Total Amount quoted in figure

2. Total Amount quoted in word

Name of the Firm with Seal & signature