

**NOTICE INVITING TENDER**  
**NO.: CUJ/OSD(PROJECT)/ 2012-13/APR-08**

Date: 19/04/2012

OSD(Project) invites on behalf of Central University of Jharkhand, Brambe, Ranchi – 835205, sealed tenders from approved and eligible manufacturers/contractors of CPWD/PWD ,and those of approved list of Central University of Jharkhand who are conversant to execute the works as under:

<b>Name of Work</b>	<b>CONSTRUCTION OF BOUNDARY WALL GATE AT CENTRAL UNIVERSITY OF JHARKHAND, BRAMBE, RANCHI.</b>
<b>Date of issue of Tender Document</b>	20/04/2012 to 11/05/2012 (9:30am to 4:30pm)
<b>Date of Submission Tender Document</b>	On 14/05/2012 upto 2:00pm at Central University of Jharkhand, City Centre, Kanke Road, Ranchi- 834008
<b>Date/Time of opening of tender</b>	On 14/05/2012 at 2:30pm
<b>Time Allowed for Completion of Project</b>	30 days
<b>Cost of Tender Document</b>	A Bank Draft for Rs. 2,000.00 (Rupees Two Thousands Only) in favor of "Central University of Jharkhand" payable at S.B.I., Upper Bazaar Branch, Ranchi be attached with the bid (non-refundable).
<b>Earnest Money</b>	2% of the quoted amount must be annexed with the Financial bid. vide Bank Draft in favor of "Central University of Jharkhand" payable at S.B.I., Upper Bazaar Branch, Ranchi

Tender document can be had from the Office of the O.S.D. (Project), Central University of Jharkhand, Kanke Road, Ranchi-834008, with written request for issuing of tender document, on all working days from the Project Office on payment of requisite cost of tender in form of Bank Draft in favor of "Central University of Jharkhand" payable at S.B.I., Upper Bazaar Branch, Ranchi or can be downloaded from university website <http://www.cuj.ac.in>.

- The tender document has to be submitted in three separate envelopes, ALL the envelopes should be enclosed in one big envelop super-scribing as  
**"TENDER DOCUMENT FOR CONSTRUCTION OF BOUNDARY WALL GATE AT CENTRAL UNIVERSITY OF JHARKHAND, BRAMBE, RANCHI"**
  - First Envelop** should be super scribed as **TECHNICAL BID** containing the technical specs and firms credential.
  - Second Envelop** should be scribed as **PRICE BID** containing the quoted rate.
  - Third Envelop** should be scribed as **EMD** containing the EMD amount.
- In case the Tender Document is downloaded from the web site then the cost of the same must be enclosed separately in **Fourth Envelop** should be scribed as **"TENDER COST"** (non-refundable) attached along with tender in the form of Demand Draft in favor of Central University of Jharkhand, payable at Ranchi.
- Tender submission should be accompanied with an Earnest Money i.e. 2% of the quoted amount (refundable) in the form of Demand Draft in favor of Central University of Jharkhand, payable at Ranchi.
- The Tender received without EMD and Cost of Tender (in case the Tender downloaded from website) shall be summarily rejected. If so desired the tenderers or their authorized representatives may be present on the day of opening of tender.
- For clarification, if any, the same may be sought from the office of the undersigned at the above address.

6. The complete tender document is to be signed with seal & is to be placed in the technical bid envelope along with the necessary required catalogues/documents. The bidder shall submit satisfactory documentary proof.
7. The tenderer should have supplied similar goods to other government organization and should produce documental evidence.
8. Central University of Jharkhand reserves the right to reject any or all prospective applicants without assigning any reason and to restrict the list of tendered contractors to any number deemed suitable by it, if too many applications are received satisfying the basic PQ criteria.
9. The decision of the Competent Authority of the University will be the final and binding to all. The Vice Chancellor, Central University of Jharkhand reserves the right to accept or reject any application and to annul the tender process and reject all applications at any time, without assigning any reason or incurring any liability to the applicants.
10. The University reserves the right to increase or decrease the scope of work or split the job. They are liable to change and must be considered only as advance information to assist the applicant.
11. If any information furnished by the applicant is found to be incorrect at a later stage, he shall be liable to be debarred from tendering/taking up of work in Central University of Jharkhand. The Central University of Jharkhand reserves the right to verify the particulars furnished by the applicant independently.
12. The rates must be quoted for service/materials F.O.R Brambe Campus of Central University of Jharkhand, situated at Brambe, Ratu-Lohardaga Road, Ranchi. No additional handling/liability charges will be entertained.
13. Even though an applicant may satisfy the above requirements, University would be liable to disqualification if he has:
  - a) Made misleading or false representation or deliberately suppressed the information in the forms, statements and enclosures required in the pre-qualification document.
  - b) Record of poor performance such as abandoning work, not properly completing the contract, or financial failures/weakness etc.

-sd-

**OSD (Project)**

**Copy To:**

- 1) *P.S to Vice Chancellor for information please. <vc@cu.j.ac.in>*
- 2) *P.S to Finance Officer for information please. <fo@cu.j.ac.in>*
- 3) *Notice Board of CUJ.*
- 4) *Executive Engineer, Project, CUJ*
- 5) *Technical Branch of Project, CUJ.*
- 6) *Accounts Branch(Project), CUJ*
- 7) *Technical Assistant, CUJ for information and necessary action to host the same in website of CUJ.<ta-computers@cu.j.ac.in>*
- 8) *Concerned file of Project.*

-sd-

**OSD (Project)**

BILL OF QUANTITY						
SL. NO.	DSR NO.	PARTICULARS	QTY.	UNIT	RATE/ UNIT	AMOUNT
1	2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.2 m in width or 10 m <sup>2</sup> on plan) including dressing of sides ramming of bottoms, liftup to 1.5 m including getting out the excavated soil and disposal of surplus excavated soil as directed. within a lead of 50 m. All kinds of soil.	11.00	m <sup>3</sup>		
2	2.25	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	11.00	m <sup>3</sup>		
3	2.27	Supplying and filling in plinth with Jamuna sand under floors including, watering, ramming consolidating and dressing complete.	0.53	m <sup>3</sup>		
4	4.1.8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size).	1.06	m <sup>3</sup>		
5	5.2.2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets etc. up to floor five level, excluding the cost of centering, shuttering and finishing 1:1½:3 (1 cement:1½ coarse sand:3 graded stone aggregate 20 mm nominal size).	2.93	m <sup>3</sup>		
6	13.4.1	12 mm cement plaster finished with cement of mix 1:4 (1 cement: 4 fine sand)	8.71	m <sup>2</sup>		
7	13.47.1	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade (Weather Coat Painting) New work (Two or more coats applied @ 1.43 ltr/ 10 sqm. over and including base coat of water proofing cement paint applied @ 2.20	8.71	m <sup>2</sup>		
8	5.22.6	Providing Tor steel reinforcement as per approved design and drawing including carriage of Rods (straight or in coils) to work site, cutting, bending and binding with annealed wire with cost of wire, removal of rust, placing the rods in position comple	340.66	kg		
9	9.48.2	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. all complete. Fixed to openings /wooden frames with rawl plugs screws etc.	504.00	kg		
10	13.48.3	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand or manufacture .	23.42	M <sup>2</sup>		

**TOTAL:** (in word) \_\_\_\_\_ (in figure) Rs. \_\_\_\_\_

**NAME OF CONTRACTOR  
(ALONG WITH DATE & SEAL)**