

**CENTRAL UNIVERSITY OF JHARKHAND,
BRAMBE, RANCHI
NOTICE INVITING QUOTATION**

NO.: CUJ /EE/Gate/ 2012-2013/13

Date:-09.10.2012

The Central University of Jharkhand, Brambe, Ranchi – 835 205, invites sealed quotation from approved and registered contractors of CPWD/PWD/Govt. Organization who are conversant to execute the works as under:

Name of Work	CONSTRUCTION OF ENTRANCE GATE AT TEMPORARY CAMPUS OF CENTRAL UNIVERSITY OF JHARKHAND.
Date of issue of Tender Document	11.10.2012 to 18.10.2012 (9:30am-4:00pm) on all working days,
Date of Submission Tender Document	19.10.2012 (up to 01:00pm)
Date/Time of opening of tender	19.10.2012 (at 02:00pm)
Time Allowed for Completion of Project	15 days
Earnest Money	At the @ of 2% of the total quoted amount by the bidder enclosed in the form of Bank Draft only in favor of Central University of Jharkhand payable at Ranchi along with bid document.

Quotation documents can be had from the Executive Engineer, Central University of Jharkhand, Brambe, Ranchi-834008, with written request for issuing of quotation document, on all working days or can be downloaded from university website <http://www.cuj.ac.in>.

1. The quotation document has to be submitted in three separate envelopes, ALL the envelopes should be enclosed in one big envelop super-scribing as **“QUOTATION DOCUMENT FOR CONSTRUCTION OF ENTRANCE GATE AT CENTRAL UNIVERSITY OF JHARKHAND, BRAMBE, RANCHI”**
 - a. **First Envelop** should be super scribed as TECHNICAL BID containing the technical specs and firms credential.
 - b. **Second Envelop** should be super scribed as PRICE BID containing the quoted rate.
 - c. **Third Envelop** should be super scribed as EMD containing the EMD amount.
2. Quotation submission should be accompanied with an Earnest Money i.e. 2% of the quoted amount (refundable) in the form of Demand Draft in favor of Central University of Jharkhand, payable at Ranchi.
3. The Quotation received without EMD shall be summarily rejected. If so desired the bidders or their authorized representatives may be present on the day of opening of quotation.
4. For clarification, if any, the same may be sought from the office of the undersigned at the above address.
5. The complete quotation document is to be signed with seal & is to be placed in the technical bid envelope along with the necessary required catalogues/documents. The bidder shall submit satisfactory documentary proof.
6. Central University of Jharkhand reserves the right to reject any or all prospective applicants without assigning any reason and to restrict the list of contractors to any

- number deemed suitable by it, if too many applications are received satisfying the basic PQ criteria.
7. The decision of the Competent Authority of the University will be the final and binding to all. Central University of Jharkhand reserves the right to accept or reject any application and to annul the quotation process and reject all applications at any time, without assigning any reason or incurring any liability to the applicants.
 8. The University reserves the right to increase or decrease the scope of work or split the job.
 9. If any information furnished by the tenderer is found to be incorrect at any stage, the tenderer shall be liable to be debarred from quoting/taking up of work in Central University of Jharkhand. The Central University of Jharkhand reserves the right to verify the particulars furnished by the tenderer independently.
 10. The rates must be quoted for service/materials F.O.R Brambe Campus of Central University of Jharkhand, situated at Brambe, Ratu-Lohardaga Road, Ranchi. No additional handling/liability charges will be entertained.
 11. Even though an applicant may satisfy the above requirements, University reserve the right to disqualify if it is found that the tenderer has:
 - a. Made misleading or false representation or deliberately suppressed the information in the forms, statements and enclosures required in the pre-qualification document.
 - b. Record of poor performance such as abandoning work, not properly completing the contract, or financial failures/weakness etc.

Registrar

BILL OF QUANTITY
FOR CONSTRUCTION OF ENTRANCE GATE AT TEMPORARY CAMPUS OF CENTRAL UNIVERSITY OF
JHARKHAND

Sl. No.	Item No.	Item	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
1.	DSR-2012 2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	M3	3.60		
2.	DSR-2012 2.25	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5m.	M3	2.40		
3.	DSR-2012 2.27	Supplying and filling in plinth with Jamuna sand under floors, including watering, ramming, consolidating and dressing complete.	M3	0.30		
4.	DSR-2012 4.1.8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:4:8 (1 Cement: 4 coarse sand: 8 graded stone aggregate 40 mm nominal size).	M3	0.30		
5.	DSR-2012 5.2.2	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. up to floor five level excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	M3	5.12		
6.	DSR-2012 5.9.1 5.9.5 5.9.6	Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete. Lintels, beams, plinth beams, girders, bressumers and cantilevers. Columns, Pillars, Piers, Abutments, Posts and Struts.	M3 M3 M3	2.70 4.41 16.74		
7.	DSR-2012 5.22.6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete up to plinth level. Thermo-Mechanically Treated bars.	Kg	208.28		
8.	DSR-2012 6.3.1	Brick work with common burnt clay machine moulded perforated bricks of class designation 12.5 conforming to IS: 2222 -1991 in superstructure above plinth level up to floor five level in cement mortar 1:6 (1 cement : 6 coarse sand) : With F.P.S.(non modular) bricks.	M3	1.08		
9.	DSR-2012 10.5.2	Providing and fixing 1mm thick M.S. sheet door with frame of 40x40x6mm angle iron and 3mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer. Using flats 30x6mm for diagonal braces and central cross piece.	M2	10.08		
10.	DSR-2012 13.4.2	12 mm cement plaster of mix : 1:6 (1 cement: 6 coarse sand)	M2	21.60		
11.	DSR-2012 13.44.1	Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @ 3.84 kg/10 sqm).	M2	21.60		
12.		TOTAL :-				

NAME OF CONTRACTOR
(ALONG WITH DATE & SEAL)