

**SHORT TENDER NOTICE**  
**NO.: CUJ/OSD(PROJECT)/2012-13/MAY-04**

Date: 26/05/2012

OSD(Project) on behalf of Central University of Jharkhand, Brambe, Ranchi – 835205, invites sealed tenders from approved and eligible contractors of CPWD/PWD, and those of approved list of Central University of Jharkhand who are conversant to execute the works as under:

<b>Name of Work</b>	<b>CONSTRUCTION OF BOUNDARY WALL AROUND GIRLS HOSTEL ZONE, DRAIN AND SOAK PIT IN CUJ, BRAMBE CAMPUS</b>
<b>Date of issue of Tender Document</b>	28/05/2012 to 02/06/2012 (9:30am to 4:30pm)
<b>Date of Submission Tender Document</b>	On 04/06/2012 upto 3:00pm at Central University of Jharkhand, City Centre, Kanke Road, Ranchi- 834008
<b>Date/Time of opening of tender</b>	On 04/06/2012 at 3:30pm
<b>Time Allowed for Completion of Project</b>	30 (Thirty) days
<b>Cost of Tender Document</b>	A Bank Draft for Rs. 5000.00 (Rupees Five Thousands Only) in favor of "Central University of Jharkhand" payable at S.B.I., Ranchi. (non-refundable).
<b>Earnest Money</b>	A Bank Draft for Rs 36,000.00 (Rupees Thirty Six Thousands Only) in favor of "Central University of Jharkhand" payable at S.B.I., Ranchi be attached with the Technical bid. (refundable).

Tender document can be had from the Office of the O.S.D. (Project), Central University of Jharkhand, Kanke Road, Ranchi-834008, with written request for issuing of tender document, on all working days from the Project Office on payment of requisite cost of tender in form of Bank Draft in favor of "Central University of Jharkhand" payable at State Bank of India, Ranchi; or can be downloaded from University website <http://www.cuj.ac.in>.

1.

- a) **First Envelop** should be super scribed as "**TECHNICAL BID**" containing the **TECHNICAL SPECS** and firms credential; **TENDER COST**, in case the Tender Document is downloaded from the web site then the cost of the same must be enclosed; and **EMD**. The **TENDER COST & EMD** should be submitted vide Bank Draft only in favor of "Central University of Jharkhand" payable at S.B.I., Upper Bazaar Branch, Ranchi
- b) **Second Envelop** should be scribed as "**PRICE BID**" containing the quoted rate.

Both the above envelops (a) & (b) should be enclosed in one big envelop super-scribing as

**"TENDER DOCUMENT FOR CONSTRUCTION OF BOUNDARY WALL AROUND GIRLS HOSTEL ZONE, DRAIN AND SOAK PIT IN CUJ, BRAMBE CAMPUS."**

2. The Tender received without EMD and Tender Cost (in case the Tender downloaded from website) shall be summarily rejected.
3. If desired the tenderers or their authorized representatives only may be present on the day of opening of tender.
4. For clarification, if any, the same may be sought from the office of the undersigned at the above address.

5. The complete tender document is to be signed with seal & is to be placed in the technical bid envelope along with the necessary required catalogues/documents. The bidder shall submit satisfactory documentary proof. Authorized distributor/Principal certificate to be enclosed.
6. The tenderer should have supplied similar goods to other government organization and should produce documental evidence.
7. Central University of Jharkhand reserves the right to reject any or all prospective applicants without assigning any reason and to restrict the list of tendered contractors to any number deemed suitable by it, if too many applications are received satisfying the basic PQ criteria.
8. The decision of the Competent Authority of the University will be the final and binding to all. The Vice Chancellor, Central University of Jharkhand reserves the right to accept or reject any application and to annul the tender process and reject all applications at any time, without assigning any reason or incurring any liability to the applicants.
9. The University reserves the right to increase or decrease the scope of work or split the job among eligible contractors. They are liable to change and must be considered only as advance information to assist the applicant.
10. If any information furnished by the applicant is found to be incorrect at a later stage, he shall be liable to be debarred from tendering/taking up of work in Central University of Jharkhand. The Central University of Jharkhand reserves the right to verify the particulars furnished by the applicant independently.
11. ***The rates must be quoted for service/materials, inclusive of all statutory taxes & levies; F.O.R City Centre, Central University of Jharkhand, situated at Brambe, Ranchi - 834008. No additional handling / liability charges will be entertained.***
12. Even though an applicant may satisfy the above requirements, University would be liable to disqualification if he has:
  - a) Made misleading or false representation or deliberately suppressed the information in the forms, statements and enclosures required in the pre-qualification document.
  - b) Record of poor performance such as abandoning work, not properly completing the contract, or financial failures/weakness etc.
13. This work is of the emergency in nature, as the work must be completed before the ensuing session i.e. before 25<sup>th</sup> June 2012.

-sd-

**OSD Project**

**Copy To:**

- 1) P.S to Vice Chancellor for information please. <vc@cuja.ac.in>
- 2) P.S to Registrar for information please. <registrar@cuja.ac.in>
- 3) P.S to Finance Officer for information please. <fo@cuja.ac.in>
- 4) OSD Planning for information and necessary action please. <osd\_planning@cuja.ac.in>
- 5) Executive Engineer, Project, CUJ.
- 6) Technical Branch of Project, CUJ.
- 7) Accounts Branch(Project), CUJ.
- 8) Technical Assistant, CUJ for information and necessary action to host the same in website of CUJ. <ta-computers@cuja.ac.in>
- 9) Notice Board of CUJ at City Centre & Brambe Campus.
- 10) Concerned file of Project.

-sd-

**(OSD Project)**

**BILL OF QUANTITY**  
**FOR CONSTRUCTION OF BOUNDARY WALL AROUND GIRLS HOSTEL ZONE,**  
**DRAIN AND SOAK PIT IN CUJ, BRAMBE CAMPUS.**

Sl.No.	DSR.NO.	ITEM DESCRIPTION	QTY.	UNIT	RATE/UNIT	AMOUNT
1.	2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	41.344	M <sup>3</sup>		
2.	4.1.8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size).	5.513	M <sup>3</sup>		
3.	5.2.2	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. up to floor five level excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	53.907	M <sup>3</sup>		
4.	6.4.2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	115.500	M <sup>3</sup>		
5.	2.25	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	41.344	M <sup>3</sup>		
6.	5.9.1	Centering and shuttering including strutting, propping etc. and removal of form for: Foundations, footings, bases of columns, etc. for mass concrete.	713.400	M <sup>2</sup>		
7.	13.4.2	12 mm cement plaster of mix : 1:6 (1 cement: 6 coarse sand)	1503.900	M <sup>2</sup>		
8.	5.22.6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars.	5695.004	KG		

9.	13.47.1	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade(Weather Coat Painting). New work (Two or more coats applied @ 1.43 ltr/ 10 sqm. over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm).	1503.900	M2		
10.	5.10.33 (JSR)	Providing 250mm wide brick drain in cement mortar (1:6) with av.250mm clear depth and 250mm apron including cost of earthwork involved with 75mm.~cement concrete (1:4:8) over one brick designation 75A flat soling in proper grade and slope at the base, the drain duly plastered in C.M.(1:3) with punning over exposed surface all complete as per building specification and direction of E/I.	235.000	M		
11.	19.32.1	Making soak pit 2.5 m diameter 3.0 metre deep with 45 x 45 cm dry brick honey comb shaft with bricks and S.W. drain pipe 100 mm diameter, 1.8 m long complete as per standard design. With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	2.000	EACH		
12.	10.25.2	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	237.258	KG		
13	13.48.3	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications: Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand or manufacture	28.350	M2		

**TOTAL:** (in word) \_\_\_\_\_ (in figure) Rs. \_\_\_\_\_

\_\_\_\_\_

**Signature of Contractor  
along with date & seal**