

NOTICE INVITING TENDER

NO.: CUJ/Deep Borewell/2013-14/21

The Central University of Jharkhand, Brame, Ranchi – 835205, invites sealed tender from approved and registered contractor of CPWD/PWD/Govt. Organisation who are conversant to execute the works as under:

Name of work	A) Flushing of 02 nos. bore well along with extra dipping of 200 feet (appx) with other accessories as mentioned at BOQ. B) Dismantling and Reassembling of existing water tower (steel frame 08 nos.) at a single place to make a centralise water supply system for boys hostel at Brambe.
Date of issue of Tender Document	15.01.2015 to 27.01.2015 (10:00 am to 4:00 pm).
Date of Submission Tender document	28.01.2015 (10:00 am to 12:00 pm).
Date/Time of opening of Tender	28.01.2015 at 02:00 PM.
Time allowed for Completion project	10 (Ten days)
Cost of Tender document (non-refundable)	Bank draft for Rs. 500.00 (Rupees Five Hundred only) in favour of "Central University of Jharkhand" payable at Ranchi.
Earnest Money	2% of total quoted amount enclosed in the form of Bank Draft only in favour of Central University of Jharkhand payable at Ranchi along with bid document.

Tender document can be had from the Executive Engineer, Central University of Jharkhand, Brambe, Ranchi-835205, on written request for issuing of tender documents, on all working days on payment of requisite cost of tender in form of Bank Draft in favour of "Central University of Jharkhand" payable at Ranchi or can be downloaded from University website <http://www.cuj.ac.in>.

1. The tender documents has to be submitted in three separate envelops, All the envelops should be enclosed in one big envelop super-scribing as

"TENDER DOCUMENTS FOR FLUSHING OF BOREWELL AND REASSEMBLING OF WATER TOWER AT CUJ, BRAMBE, RANCHI "

- a). **First Envelop** should be super-scribed as TECHNICAL BID containing the technical specification and firms credential.
 - b). **Second Envelop** should be super scribed as PRICE BID containing the quoted rate.
 - c). **Third Envelop** should be super scribed as EMD containing the EMD amount.
2. In case the Tender Document is downloaded from the website the cost of the tender document must be enclosed separately in **Fourth Envelop** super scribing as **“TENDER COST”** (non-refundable) attached along with tender in the form of Demand Draft in favour of Central University of Jharkhand, payable at Ranchi.
 3. Tender submission should be accompanied with an Earnest Money with 2% of total quoted amount (refundable) in the form of Demand Draft in favour of Central University of Jharkhand, payable at Ranchi.
 4. The Tender received without EMD and Cost of Tender Document (in case the Tender downloaded from website) shall be summarily rejected. Tenderer or their authorised representative may be present on the day of opening of tender.
 5. For clarification, if any, the same may be sought from the office of the Undersigned at the above address.
 6. The complete tender documents are to be signed with seal and to be placed in the technical bid envelope along with necessary required catalogues/documents. The bidder shall submit satisfactory documentary proof.
 7. Central University of Jharkhand reserves the right to reject any or all prospective applicants without assigning any reason and to restrict the list of tendered contractors to any number deemed suitable by it, if too many applications are received satisfying the basic prequalification criteria.
 8. The decision of the Competent Authority of the University will be final and binding to all. Central University of Jharkhand reserve the right to accept or reject any tender and to annul the tender process and reject all tenders at any time, without assigning any reason.
 9. The University reserves the right to increase or decrease the scope of work or split the job.
 10. If any information furnished by the tenderer is found to be incorrect at any stage, the tenderer shall be liable to be debarred from tendering/taking up of work in Central University of Jharkhand. The Central University of Jharkhand reserves the right to verify the particulars furnished by the tenderer, independently.
 11. The rate must be quoted for service/material F.O.R Brambe Campus of Central University of Jharkhand, situated at Brambe, Ratu-Lohadaga Road, Ranchi. No additional handling/liability charges will be entertained.
 12. Even though applicant may satisfy the above requirement, University reserve the right to disqualify if it is found that the tenderer has:
 - a. Made misleading or false representation or deliberately suppressed the information in the form of statement and enclosure required in the prequalification document.

b. Suppressed/hided the Record of proof performance such as abandoning work, not properly completing the contract, or financial failures/weakness etc.

**Following Documentary
proof Required For
Technical Document**

- a. Name of the Agencies/ Firms (Full address with Tel. No. and e -mail address)
- b. Registration No. of the Agencies/Firms and Registered with (details)
- c. Whether Registered with Labour Deptt.
- d. PAN No.

- e. Experience (Please attach job completion certificate).

-Sd-

OSD (Project)

BOQ

(A) Name of Work:- Flushing of TWO existing borewell along with drilling approf 200 feet near E- block boys hostel and block 6 girls hostel at CUJ, Brambe campus.

Sl. No.	Item Nos.	Item of works	Nos.	Qty.	Unit	Rate	AMOUNT(IN Rs.)
1	NDSR	Flushing of exiting borewell of depth approx 300 feet	2	500	feet		
	a	6 1/2" dia Deep Bore Well supplying all materials labour and tools and equipment for drilling 6 1/2" dia bore well in any kind of sell rock by using DTH supper rig machine and bell hammer technology					
	b	From 300' to 600' below G.L.	2	100.00	P/F		
	c	From 600' to 700' below G.L.	2	100.00	P/F		
2	NDSR	Supplying & lowering 40 mm dia column pipe with all complete job.	2	60.96	m		
3	NDSR	Cost of 4 sqm x 3- core Copper.	2	60.96	m		
4	NDSR	Cost of supply of submersible pump set (3H P, 3 Phase) type cora 2c/33+UMAI 100 Head RANGE IN Metre 180-134-72 Discharge in m3/hr. 1.1-2.0-2.8	2	1.00	each		
5	18.12.4	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc.32 mm dia nominal bore	1	609.60	m		
6	18.17.2	Providing and fixing brass stop cock of approved quality : 32 mm nominal bore.	1	9.00	each		
						TOTAL =	

BOQ

B) Name of work:- DISMANTLING AND REASSEMBLING OF WATER TOWER INCLUDING FOUNDATION

SL NO.	DSR-2014	ITEMS	QTY	UNIT	RATE	AMOUNT (IN Rs)
1	15.18	Dismantling steel work in built up sections in angles, tees, flats and channels including all gusset plates, bolts, nuts, cutting rivets, welding etc. including dismembering and stacking within 50metres lead.	40000	kg		
2	15.22	Extra for marking of structural steel work required to be re-erected.	40000	kg		
3	11.35	Providing and fixing M.S. angle 50x50x5 mm to act as nosing with lugs of M.S. flat 10x5 mm, 10 cm long, forked at end 60cm apart (minimum three lugs to be provided), including necessary welding and applying a priming coat of approved primer on exposed surface etc. complete.	600	kg		
4	2.6.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth. 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed.All kinds of soil	10.87	m3		
5	4.1.8	1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) aggregate 40 mm nominal size)	0.9	m3		
6	6.12.2	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundations and plinth in :cement mortar 1:4 (1 cement : 4 coarse sand)	33.44	m2		
7	5.3	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement, with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	1.4	m3		
		TOTAL				

TOTAL AMOUNT IN FIGURE (A+B)

TOTAL AMOUNT IN WORD (A+B) (IN RS)

NAME OF CONTRACTOR
ALONG WITH SIGN AND SEAL