

CENTRAL UNIVERSITY OF JHARKHAND

BRAMBE, RANCHI

NOTICE INVITING TENDER

NO.: CUJ/EE /CIVIL WORK/2013-2014/ 11

The Central University of Jharkhand, Brame, Ranchi – 835205, invites sealed tender from approved and registered contractor of CPWD/PWD/Govt. Organisation who are conversant to execute the works as under:

Name of work	CONSTRUCTION OF KITCHEN PLATFORM, UTENSIL WASHING AREA, NEW OPEN DRAIN, GARBAGE BURNING PIT AND GARBAGE BIODEGRADABLE PIT AT CUJ, BRAMBE CAMPUS.
Date of issue of Tender Document	10.01.2014 to 16.01.2014 (10:00 am to 4:00 pm).
Date of Submission Tender document	17.01.2014 (10:00 am to 12:30 pm).
Date/Time of opening of Tender	17.01.2014 at 3:00 pm.
Time allowed for Completion project	45 (Forty Five) days.
Cost of Tender document (non-refundable)	Bank draft for Rs. 500.00 (Rupees Five Hundred only) in favour of "Central University of Jharkhand" payable at Ranchi.
Earnest Money	2% of total quoted amount enclosed in the form of Bank Draft only in favour of Central University of Jharkhand payable at Ranchi along with bid document.

Tender document can be had from the Executive Engineer, Central University of Jharkhand, Brambe, Ranchi-835205, on written request for issuing of tender documents, on all working days on payment of requisite cost of tender in form of Bank Draft in favour of "Central University of Jharkhand" payable at Ranchi or can be downloaded from University website <http://www.cuj.ac.in>.

1. The tender documents has to be submitted in three separate envelops, All the envelops should be enclosed in one big envelop super-scribing as

“TENDER DOCUMENTS FOR CONSTRUCTION OF KITCHEN PLATFORM, UTENSIL WASHING AREA, NEW OPEN DRAIN, GARBAGE BURNING PIT AND GARBAGE BIODEGRADABLE PIT AT CENTRAL UNIVERSITY OF JHARKHAND, BRAMBE, RANCHI “

- a). **First Envelop** should be super-scribed as TECHNICAL BID containing the technical specification and firms credential.
 - b). **Second Envelop** should be super scribed as PRICE BID containing the quoted rate.
 - c). **Third Envelop** should be super scribed as EMD containing the EMD amount.
2. In case the Tender Document is downloaded from the website the cost of the tender document must be enclosed separately in **Fourth Envelop** super scribing as **“TENDER COST”** (non-refundable) attached along with tender in the form of Demand Draft in favour of Central University of Jharkhand, payable at Ranchi.
 3. Tender submission should be accompanied with an Earnest Money with 2% of total quoted amount (refundable) in the form of Demand Draft in favour of Central University of Jharkhand, payable at Ranchi.
 4. The Tender received without EMD and Cost of Tender Document (in case the Tender downloaded from website) shall be summarily rejected. Tenderer or their authorised representative may be present on the day of opening of tender.
 5. For clarification, if any, the same may be sought from the office of the Undersigned at the above address.
 6. The complete tender documents are to be signed with seal and to be placed in the technical bid envelope along with necessary required catalogues/documents. The bidder shall submit satisfactory documentary proof.
 7. Central University of Jharkhand reserves the right to reject any or all prospective applicants without assigning any reason and to restrict the list of tendered contractors to any number deemed suitable by it, if too many applications are received satisfying the basic prequalification criteria.
 8. The decision of the Competent Authority of the University will be final and binding to all. Central University of Jharkhand reserve the right to accept or reject any tender and to annul the tender process and reject all tenders at any time, without assigning any reason.
 9. The University reserves the right to increase or decrease the scope of work or split the job.
 10. If any information furnished by the tenderer is found to be incorrect at any stage, the tenderer shall be liable to be debarred from tendering/taking up of work in Central University of Jharkhand. The Central University of Jharkhand reserves the right to verify the particulars furnished by the tenderer, independently.
 11. The rate must be quoted for service/material F.O.R Brambe Campus of Central University of Jharkhand, situated at Brambe, Ratu-Lohadaga Road, Ranchi. No additional handling/liability charges will be entertained.

12. Even though applicant may satisfy the above requirement, University reserve the right to disqualify if it is found that the tenderer has:

a. Made misleading or false representation or deliberately suppressed the information in the form of statement and enclosure required in the prequalification document.

b. Suppressed/hided the Record of proof performance such as abandoning work, not properly completing the contract, or financial failures/weakness etc.

**Following Documentary
proof Required For
Technical Document**

a. Name of the Agencies/ Firms (Full address with Tel. No. and e -mail address)

b. Registration No. of the Agencies/Firms and Registered with (details)

c. Whether Registered with Labour Deptt.

d. PAN No.

e. Financial Status of Bidder including Balance Sheet of past 3 years duly authenticated by the Chartered Accountant

f. Experience (Please attach job completion certificate).

S/d

OSD (Project)

BOQ**For Construction of New Open Drain (1 nos.) around Boy's Hostel at CUJ, Brambe .**

Sl.No.	DSR-2012	Items Description	QTY.	Unit.	Rate.	Amount.
1	2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	67.10	m3		
2	6.1.2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:Cement mortar 1:6 (1 cement : 6 coarse sand)	28.98	m3		
3	4.1.11	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level (a) 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)	8.24	m3		
4	13.1.1	12 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand)	225.70	m2		
5	13.43.1	Neat cement punning	225.70	m2		
6	19.32.1	Making soak pit 2.5 m diameter 3.0 metre deep with 45 x 45 cm dry brick honey comb shaft with bricks and S.W. drain pipe 100 mm diameter, 1.8 m long complete as per standard design. With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	1.00	Each		
TOTAL						

TOTAL (IN FIGURE)

TOTAL (IN WORD)

NAME OF CONTRACTOR

(ALONG WITH DATE AND SEAL)

BOQ

For Construction of Kitchen Platform (1 nos.) Boy's Mess at CUJ, Brambe .

Sl.No.	DSR-2012	Items Description	QTY.	Unit.	Rate.	Amount.
1	6.1.2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:Cement mortar 1:6 (1 cement : 6 coarse sand)	3.41	m3		
2	5.3	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement, with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	0.90	m3		
3	5.9.5	Centering and shuttering including strutting, propping etc. and removal of form for: Lintels, beams, plinth beams, girders, bressumers and cantilevers.	8.40	m2		
4	8.2.2.2	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills , facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Raj Nagar Plain white marble/ Udaipur green marble/ Zebra black marble Area of slab above 0.50 sqm	11.97	m2		
5	13.1.2	12 mm cement plaster of mix :1:6 (1 cement: 6 fine sand)	30.24	m2		
6	22.5.6	Reinforcement for R.C.C. works including straightening, cutting, bending, placing in position and binding all complete. Thermo-Mechanically Treated bars. (TMT)	51.52	Kg		
7	13.44.1	Finishing walls with water proofing cement paint of required shade: New work (Two or more coats applied @ 3.84 kg/10 sqm).	30.24	m2		
8	13.82.2	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour.Two coats	30.24	m2		
TOTAL						

TOTAL (IN FIGURE)

TOTAL (IN WORD)

NAME OF CONTRACTOR
(ALONG WITHDATE AND SEAL)

BOQ
FOR CONSTRUCTION OF WASHING AREA (2 nos.) AT CAMPUS OF CENTRAL UNIVERSITY OF JHARKHAND,

Sl.No.	DSR-2012 IT.NO.	Items Description	QTY.	Unit.	Rate.	Amount.
1	2.27	Supplying and filling in plinth with Jamuna sand under floors, including watering, ramming, consolidating and dressing complete.	7.17	CUM		
2	4.1.8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement: 4 coarse sand: 8 graded stone aggregate 40 mm nominal size).	1.92	CUM		
3	4.1.5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	0.17	CUM		
4	6.1.2	Brick work with F.P.S. bricks of class designation 75 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	13.54	CUM		
5	12.5	Providing & fixing of pre-coated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm +/- 5% total coated thickness (TCT) thick Zinc coating 120gsm as per IS: 277 in 240mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches while transportation and should be supplied in single length up to 12 meter or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55mm) with EPDM seal or with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead complete up to any pitch in horizontal/ vertical or curved surfaces excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	27.52	SQ.M		
6	13.1.2	12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	61.08	SQ.M		
7	13.44.1	Finishing walls with water proofing cement paint of required shade: New work (Two or more coats applied @ 3.84 kg/10 sqm).	61.08	SQ.M		
8	13.56.1	Painting (two or more coats) on rain water, soil, waste and vent pipes and fittings with synthetic enamel paint of approved brand and manufacture and required colour over a priming coat of approved steel primer on new work. 100 mm diameter pipes	61.08	M		
9	18.49.1	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 15 mm nominal bore.	2.00	EACH		

10	18.10.3	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. Internal work - Exposed on wall 25 mm dia nominal bore	55.00	M		
----	---------	---	-------	---	--	--

Total =

TOTAL (IN FIGURE)

TOTAL (IN WORD)

NAME OF CONTRACTOR

(ALONG WITH DATE AND SEAL)

Cost of Abstract

For Construction of Garbage pit (1 nos.) around Boy's Hostel at CUJ, Brambe .

Sl.No.	DSR-2012	Items Description	QTY.	Unit.	Rate.	Amount.
1	4.1.11	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level (a) 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)	2.00	m3		
2	6.1.2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:Cement mortar 1:6 (1 cement : 6 coarse sand)	4.11	m3		
TOTAL						

TOTAL (IN FIGURE)

TOTAL (IN WORD)

NAME OF CONTRACTOR

(ALONG WITH DATE AND SEAL)

Cost of Abstract

For Construction of Biodegradable Garbage pit (1 nos.) around Boy's Hostel at CUJ, Brambe .

Sl.No.	DSR-2012	Items Description	QTY.	Unit.	Rate.	Amount.
2	6.1.2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:Cement mortar 1:6 (1 cement : 6 coarse sand)	4.11	m3		
TOTAL						

TOTAL (IN FIGURE)

TOTAL (IN WORD)

NAME OF CONTRACTOR

(ALONG WITHDATE AND SEAL)