

NOTICE INVITING TENDER
NO.: CUJ/OSD(PROJECT)/2011-12/014-005

Date: 03/05/2012

O/o OSD(Project) on behalf of Central University of Jharkhand, Ranchi, invites sealed tenders from approved and eligible contractors of CPWD/PWD ,and those of approved list of Central University of Jharkhand who are conversant to execute the works as under:

Name of Work	CONSTRUCTION OF TRACKING PATH, SEWERAGE LINE AND WATER SUPPLY LINE FOR HOSTEL BUILDING AT CENTRAL UNIVERSITY OF JHARKHAND CAMPUS, BRAMBE, RANCHI
Date of issue of Tender Document	04/05/2012 to 25/05/2012 (9:30am to 4:30pm)
Date of Submission Tender Document	On 28/05/2012 upto 1:00pm at Central University of Jharkhand, City Centre, Kanke Road, Ranchi- 834008
Date/Time of opening of tender	On 28/05/2012 at 2:30pm
Time Allowed for Completion of Project	30 days
Cost of Tender Document	A Bank Draft for Rs.5,000.00 (Rupees Five Thousands only) in favor of "Central University of Jharkhand" payable at S.B.I., Upper Bazaar Branch, Ranchi be attached with the bid (non-refundable).
Earnest Money	Rs. 35,000.00 (Rupees Thirty Five Thousands only) must be annexed with the Financial bid. vide Bank Draft in favor of "Central University of Jharkhand" payable at S.B.I., Upper Bazaar Branch, Ranchi

Tender document can be had from the Office of the O.S.D. (Project), Central University of Jharkhand, Kanke Road, Ranchi-834008, with written request for issuing of tender document, on all working days from the Project Office on payment of requisite cost of tender in form of Bank Draft in favor of "Central University of Jharkhand" payable at S.B.I., Upper Bazaar Branch, Ranchi or can be downloaded from university website <http://www.cuj.ac.in>.

1.

(a) **First Envelop** should be super scribed as "**TECHNICAL BID**" containing the **TECHNICAL SPECS** and firms credential; **TENDER COST**, in case the Tender Document is downloaded from the web site then the cost of the same must be enclosed; and **EMD**. The **TENDER COST & EMD** should be submitted vide Bank Draft only in favor of "Central University of Jharkhand" payable at S.B.I., Upper Bazaar Branch, Ranchi

(b) **Second Envelop** should be scribed as "**PRICE BID**" containing the quoted rate.

Both the above envelops (a) & (b) should be enclosed in one big envelop super-scribing as

**"TENDER DOCUMENT FOR CONSTRUCTION OF TRACKING PATH,
SEWERAGE LINE AND WATER SUPPLY LINE FOR HOSTEL BUILDING AT
CENTRAL UNIVERSITY OF JHARKHAND CAMPUS, BRAMBE, RANCHI."**

2. The Tender received without EMD and Tender Cost (in case the Tender downloaded from website) shall be summarily rejected.

3. If desired the tenderers or their authorized representatives only may be present on the day of opening of tender.
4. For clarification, if any, the same may be sought from the office of the undersigned at the above address.
5. The complete tender document is to be signed with seal & is to be placed in the technical bid envelope along with the necessary required catalogues/documents. The bidder shall submit satisfactory documentary proof. Authorized distributor/Principal certificate to be enclosed.
6. The tenderer should have supplied similar goods to other government organization and should produce documental evidence.
7. Central University of Jharkhand reserves the right to reject any or all prospective applicants without assigning any reason and to restrict the list of tendered contractors to any number deemed suitable by it, if too many applications are received satisfying the basic PQ criteria.
8. The decision of the Competent Authority of the University will be the final and binding to all. The Vice Chancellor, Central University of Jharkhand reserves the right to accept or reject any application and to annul the tender process and reject all applications at any time, without assigning any reason or incurring any liability to the applicants.
9. The University reserves the right to increase or decrease the scope of work or split the job. They are liable to change and must be considered only as advance information to assist the applicant.
10. If any information furnished by the applicant is found to be incorrect at a later stage, he shall be liable to be debarred from tendering/taking up of work in Central University of Jharkhand. The Central University of Jharkhand reserves the right to verify the particulars furnished by the applicant independently.
11. ***The rates must be quoted for service/materials F.O.R Brambe Campus of Central University of Jharkhand, situated at Brambe, Ratu-Lohardaga Road, Ranchi. No additional handling / liability charges will be entertained.***
12. Even though an applicant may satisfy the above requirements, University would be liable to disqualification if he has:
 - a) Made misleading or false representation or deliberately suppressed the information in the forms, statements and enclosures required in the pre-qualification document.
 - b) Record of poor performance such as abandoning work, not properly completing the contract, or financial failures/weakness etc.

-sd-
Executive Engineer

BILL OF QUANTITY

ITEM RATE FOR CONSTRUCTION OF TRACKING PATH , SEWERAGE LINE & WATER SUPPLY LINE FOR HOSTEL BUILDING AT CENTRAL UNIVERSITY OF JHARKHAND CAMPUS BREMBE, RANCHI.

SL. NO	DSR NO.	PARTICULERS	QTY.	UNIT	RATE / UNIT	AMOUNT
1	NS	Providing & fixing of PVC pipe for WC/ Bath and sewerage line including cutting trenching & back fillin ----- do. ----- do. ----- all complete job.				
		75 mm dia.	88.000	m		
		100 mm dia.	112.600	m		
		150 mm dia.	382.500	m		
2	18.12	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc.				
	18.12.3	25 mm dia.	93.500	m		
	18.12.5	40 mm dia.	982.000	m		
3	18.17.1	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end)	11.000	Each		
4	18.36.1	Constructing masonry Chamber 60x60x75 cm, inside with 75 class designation brick work in cement mortar 1:4 (1 cement : 4 coarse sand) for fire hydrants, with C.I. surface box 350x350 mm. top and 165 mm deep (inside) with chained lid and RCC top slab 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) necessary excavation foundation concrete 1:5:10 (1 cement : 5 fine sand:10 graded stone aggregate 40 mm nominal size) and inside lastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12 mm thick finished with a floating coat of neat cement complete as per standard design With F.P.S. bricks	156.000	Each		
5	2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains (not exceding 1.2 m in width or 10 m ² on plan) including dressing of sides ramming of bottoms, liftup to 1.5 m including getting out the excavated soil and disposal of surplus excavated soil as directed. within a lead of 50 m. All kinds of soil.	20.906	m ³		
6	11.59	Supplying stone dust under floors with all complete job.	140.962	m ³		
7	4.1.8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size).	13.937	m ³		
8	6.1.2	Brick work with F.P.S. bricks of class designation 75 in foundation and plinth in Cement mortar 1:6 (1 cement : 6 coarse sand)	41.812	m ³		
9	4.1.3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	0.997	m ³		